

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

Selected Sections: 02000 Misc. Bid Items, 09900 Painting, 09950 Wall Covering

Selected Typical Areas: UNIT A1, UNIT A2, UNIT B1, UNIT B2, UNIT B3, UNIT B4, UNIT B5, UNIT B7, UNIT B6

Selected Areas: (unassigned), BASEMENT, Floor 1, Floor 2, Floor 3, PUBLIC AREA DOORS/FRAMES, EXTERIOR ELEVATIONS, INTERIOR WINDOWS & WINDOW TRIM, STAIRS

Estimator:  
Job Class:  
Wage Type: **Open**

Job Status: **PENDING**  
Bid Date/Time: **6/11/2014 12:00:00 PM**  
Plans Date: **6/11/2014**

WITH PRIME

### UNIT A1 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
2 UNIT WOOD BASE PTD., 6", 220 LF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	150.00 LF	1.47	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	1.47	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	1.47	1.00	INTERIOR PAINTER
12 UNIT DW CLG. PTD. FLAT, , 691 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER	400.00 SF	1.73	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	1.73	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	1.73	1.00	INTERIOR CEILING PAINTER
13 9'1" UNIT BATH DW WALLS LSG, 9' 1", 288 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	0.72	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	0.72	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	0.72	1.00	INTERIOR WALLS PAINTER
14 9'1" UNIT DW WALLS LES, 9' 1", 2002 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	5.01	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	5.01	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	5.01	1.00	INTERIOR WALLS PAINTER
21 01 TYPE A UNIT ENTRY HM DOOR FRAME & WOOD DOOR PTD., 7' 0", 1 EA				
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	1.00	1.00	DOOR & FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
22 ACCESS PANEL, 7' 0", 1 EA				
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	0.32	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	0.32	1.00	MISCELLANEOUS TRIM PAINTER
24 03 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 3 EA				

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### UNIT A1 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT. LATEX PRIMER SEALER	1.25 EA	2.40	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	2.40	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
25 05 TYPECC UNIT DBL.WOOD DOOR FRAME & DOOR PTD., 7' 0", 1 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT. LATEX PRIMER SEALER	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
26 06 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 1 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT. LATEX PRIMER SEALER	1.25 EA	0.80	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
32 02 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 3 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT. LATEX PRIMER SEALER	1.25 EA	2.40	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	2.40	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
44 4' UNIT DW WALLS LES, 4' 0", 23 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	0.06	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	0.06	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	0.06	1.00	INTERIOR WALLS PAINTER

### UNIT A2 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
2 UNIT WOOD BASE PTD., 6", 221 LF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	150.00 LF	1.47	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	1.47	1.00	INTERIOR PAINTER

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### UNIT A2 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	1.47	1.00	INTERIOR PAINTER
12 UNIT DW CLG. PTD. FLAT, , 687 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER	400.00 SF	1.72	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	1.72	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	1.72	1.00	INTERIOR CEILING PAINTER
13 9'1" UNIT BATH DW WALLS LSG, 9' 1", 216 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	0.54	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	0.54	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	0.54	1.00	INTERIOR WALLS PAINTER
14 9'1" UNIT DW WALLS LES, 9' 1", 2004 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	5.01	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	5.01	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	5.01	1.00	INTERIOR WALLS PAINTER
21 01 TYPE A UNIT ENTRY HM DOOR FRAME & WOOD DOOR PTD., 7' 0", 1 EA				
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	1.00	1.00	DOOR & FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
22 ACCESS PANEL, 7' 0", 1 EA				
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	0.32	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	0.32	1.00	MISCELLANEOUS TRIM PAINTER
24 03 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 3 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	2.40	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	2.40	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
25 05 TYPECC UNIT DBL.WOOD DOOR FRAME & DOOR PTD., 7' 0", 1 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### UNIT A2 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
31 07 UNIT TYPE B WOOD FRAME & WOOD DOOR PTD., 7' 0", 1 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	0.80	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
32 02 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 2 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
44 4' UNIT DW WALLS LES, 4' 0", 27 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	0.07	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	0.07	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	0.07	1.00	INTERIOR WALLS PAINTER

### UNIT B1 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
2 UNIT WOOD BASE PTD., 6", 611 LF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	150.00 LF	4.07	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	4.07	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	4.07	1.00	INTERIOR PAINTER
12 UNIT DW CLG. PTD. FLAT, , 3923 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER	400.00 SF	9.81	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	9.81	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	9.81	1.00	INTERIOR CEILING PAINTER
13 9'1" UNIT BATH DW WALLS LSG, 9' 1", 1000 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	2.50	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	2.50	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	2.50	1.00	INTERIOR WALLS PAINTER
14 9'1" UNIT DW WALLS LES, 9' 1", 5546 SF				

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

**UNIT B1 (quantities and amounts below reflect a single build of this typical area)**

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	13.87	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	13.87	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	13.87	1.00	INTERIOR WALLS PAINTER
21 01 TYPE A UNIT ENTRY HM DOOR FRAME & WOOD DOOR PTD., 7' 0", 1 EA				
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	1.00	1.00	DOOR & FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
22 ACCESS PANEL, 7' 0", 1 EA				
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	0.32	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	0.32	1.00	MISCELLANEOUS TRIM PAINTER
24 03 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 3 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	2.40	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	2.40	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
26 06 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 1 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	0.80	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
28 04 UNIT TYPE C WOOD FRAME & WOOD DOOR PTD., 7' 0", 2 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	1.33	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	1.33	1.00	MISCELLANEOUS TRIM PAINTER
29 08 UNIT TYPE BB DBL. WOOD FRAME & DBL. WOOD DOOR PTD., 7' 0", 1 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### UNIT B1 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
32 02 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 5 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	4.00	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	4.00	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	2.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	2.67	1.00	MISCELLANEOUS TRIM PAINTER

### UNIT B2 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
2 UNIT WOOD BASE PTD., 6", 623 LF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	150.00 LF	4.15	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	4.15	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	4.15	1.00	INTERIOR PAINTER
12 UNIT DW CLG. PTD. FLAT, , 4218 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER	400.00 SF	10.55	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	10.55	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	10.55	1.00	INTERIOR CEILING PAINTER
13 9'1" UNIT BATH DW WALLS LSG, 9' 1", 835 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	2.09	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	2.09	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	2.09	1.00	INTERIOR WALLS PAINTER
14 9'1" UNIT DW WALLS LES, 9' 1", 5656 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	14.14	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	14.14	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	14.14	1.00	INTERIOR WALLS PAINTER
21 01 TYPE A UNIT ENTRY HM DOOR FRAME & WOOD DOOR PTD., 7' 0", 1 EA				
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	1.00	1.00	DOOR & FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
22 ACCESS PANEL, 7' 0", 1 EA				

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### UNIT B2 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	0.32	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	0.32	1.00	MISCELLANEOUS TRIM PAINTER
24 03 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 3 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	2.40	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	2.40	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
25 05 TYPECC UNIT DBL.WOOD DOOR FRAME & DOOR PTD., 7' 0", 1 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
31 07 UNIT TYPE B WOOD FRAME & WOOD DOOR PTD., 7' 0", 1 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	0.80	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
32 02 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 4 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	2.13	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	2.13	1.00	MISCELLANEOUS TRIM PAINTER

### UNIT B3 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
2 UNIT WOOD BASE PTD., 6", 641 LF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	150.00 LF	4.28	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	4.28	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	4.28	1.00	INTERIOR PAINTER

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

**UNIT B3 (quantities and amounts below reflect a single build of this typical area)**

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
12 UNIT DW CLG. PTD. FLAT, , 4185 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER	400.00 SF	10.46	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	10.46	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	10.46	1.00	INTERIOR CEILING PAINTER
13 9'1" UNIT BATH DW WALLS LSG, 9' 1", 789 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	1.97	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	1.97	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	1.97	1.00	INTERIOR WALLS PAINTER
14 9'1" UNIT DW WALLS LES, 9' 1", 5826 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	14.56	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	14.56	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	14.56	1.00	INTERIOR WALLS PAINTER
21 01 TYPE A UNIT ENTRY HM DOOR FRAME & WOOD DOOR PTD., 7' 0", 1 EA				
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	1.00	1.00	DOOR & FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
22 ACCESS PANEL, 7' 0", 1 EA				
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	0.32	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	0.32	1.00	MISCELLANEOUS TRIM PAINTER
24 03 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 3 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	2.40	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	2.40	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
25 05 TYPECC UNIT DBL.WOOD DOOR FRAME & DOOR PTD., 7' 0", 1 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER



# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### UNIT B3 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
31 07 UNIT TYPE B WOOD FRAME & WOOD DOOR PTD., 7' 0", 1 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	0.80	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
32 02 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 4 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	2.13	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	2.13	1.00	MISCELLANEOUS TRIM PAINTER

### UNIT B4 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
2 UNIT WOOD BASE PTD., 6", 612 LF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	150.00 LF	4.08	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	4.08	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	4.08	1.00	INTERIOR PAINTER
12 UNIT DW CLG. PTD. FLAT, , 3984 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER	400.00 SF	9.96	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	9.96	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	9.96	1.00	INTERIOR CEILING PAINTER
13 9'1" UNIT BATH DW WALLS LSG, 9' 1", 767 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	1.92	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	1.92	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	1.92	1.00	INTERIOR WALLS PAINTER
14 9'1" UNIT DW WALLS LES, 9' 1", 5561 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	13.90	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	13.90	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	13.90	1.00	INTERIOR WALLS PAINTER
21 01 TYPE A UNIT ENTRY HM DOOR FRAME & WOOD DOOR PTD., 7' 0", 1 EA				

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### UNIT B4 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	1.00	1.00	DOOR & FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
22 ACCESS PANEL, 7' 0", 1 EA				
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	0.32	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	0.32	1.00	MISCELLANEOUS TRIM PAINTER
23 09 TYPE BB UNIT DBL.WOOD DOOR FRAME & DBL. WOOD DOOR PTD., 7' 0", 2 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	1.60	1.00	WOOD DOOR/FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	1.60	1.00	WOOD DOOR/FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
24 03 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 1 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	0.80	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
25 05 TYPECC UNIT DBL.WOOD DOOR FRAME & DOOR PTD., 7' 0", 1 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
26 06 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 1 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	0.80	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### UNIT B4 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
31 07 UNIT TYPE B WOOD FRAME & WOOD DOOR PTD., 7' 0", 2 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT. LATEX PRIMER SEALER	1.25 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
32 02 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 4 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT. LATEX PRIMER SEALER	1.25 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	2.13	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	2.13	1.00	MISCELLANEOUS TRIM PAINTER

### UNIT B5 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
2 UNIT WOOD BASE PTD., 6", 612 LF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	150.00 LF	4.08	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	4.08	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	4.08	1.00	INTERIOR PAINTER
12 UNIT DW CLG. PTD. FLAT, , 3939 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER	400.00 SF	9.85	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	9.85	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	9.85	1.00	INTERIOR CEILING PAINTER
13 9'1" UNIT BATH DW WALLS LSG, 9' 1", 898 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	2.25	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	2.25	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	2.25	1.00	INTERIOR WALLS PAINTER
14 9'1" UNIT DW WALLS LES, 9' 1", 5558 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	13.89	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	13.89	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	13.89	1.00	INTERIOR WALLS PAINTER
21 01 TYPE A UNIT ENTRY HM DOOR FRAME & WOOD DOOR PTD., 7' 0", 1 EA				
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	1.00	1.00	DOOR & FRAME PAINTER

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### UNIT B5 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
22 ACCESS PANEL, 7' 0", 1 EA				
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	0.32	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	0.32	1.00	MISCELLANEOUS TRIM PAINTER
24 03 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 3 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.25 EA	2.40	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	2.40	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
25 05 TYPECC UNIT DBL.WOOD DOOR FRAME & DOOR PTD., 7' 0", 1 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
31 07 UNIT TYPE B WOOD FRAME & WOOD DOOR PTD., 7' 0", 1 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.25 EA	0.80	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
32 02 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 4 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.25 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	2.13	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	2.13	1.00	MISCELLANEOUS TRIM PAINTER
44 4' UNIT DW WALLS LES, 4' 0", 77 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	0.19	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	0.19	1.00	INTERIOR WALLS PAINTER

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### UNIT B5 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	0.19	1.00	INTERIOR WALLS PAINTER

### UNIT B7 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
----------------------	------------	------------	------	-----------

#### 2 UNIT WOOD BASE PTD., 6", 248 LF

PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	150.00 LF	1.65	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	1.65	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	1.65	1.00	INTERIOR PAINTER

#### 12 UNIT DW CLG. PTD. FLAT, , 1110 SF

PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER	400.00 SF	2.77	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	2.77	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	2.77	1.00	INTERIOR CEILING PAINTER

#### 13 9'1" UNIT BATH DW WALLS LSG, 9' 1", 431 SF

PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	1.08	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	1.08	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	1.08	1.00	INTERIOR WALLS PAINTER

#### 14 9'1" UNIT DW WALLS LES, 9' 1", 2985 SF

PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	7.46	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	7.46	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	7.46	1.00	INTERIOR WALLS PAINTER

#### 21 01 TYPE A UNIT ENTRY HM DOOR FRAME & WOOD DOOR PTD., 7' 0", 1 EA

PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	1.00	1.00	DOOR & FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER

#### 24 03 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 4 EA

PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT. LATEX PRIMER SEALER	1.25 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	2.13	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	2.13	1.00	MISCELLANEOUS TRIM PAINTER

#### 25 05 TYPECC UNIT DBL.WOOD DOOR FRAME & DOOR PTD., 7' 0", 1 EA

PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT. LATEX PRIMER SEALER	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
--	---------	------	------	-------------------------

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### UNIT B7 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
32 02 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 4 EA				
PRIME - Apply Primer, PREPRITE PROBLOK INT./EXT. LATEX PRIMER SEALER	1.25 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	2.13	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	2.13	1.00	MISCELLANEOUS TRIM PAINTER

### UNIT B6 (quantities and amounts below reflect a single build of this typical area)

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
2 UNIT WOOD BASE PTD., 6", 584 LF				
PRIME - Apply Primer, PREPRITE PROBLOK INT/EXT LATEX PRIMER/SEALER	150.00 LF	3.90	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	3.90	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	3.90	1.00	INTERIOR PAINTER
12 UNIT DW CLG. PTD. FLAT, , 4016 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER	400.00 SF	10.04	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	10.04	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	10.04	1.00	INTERIOR CEILING PAINTER
13 9'1" UNIT BATH DW WALLS LSG, 9' 1", 837 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	2.09	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	2.09	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	2.09	1.00	INTERIOR WALLS PAINTER
14 9'1" UNIT DW WALLS LES, 9' 1", 5305 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	13.26	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	13.26	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	13.26	1.00	INTERIOR WALLS PAINTER
21 01 TYPE A UNIT ENTRY HM DOOR FRAME & WOOD DOOR PTD., 7' 0", 1 EA				
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	1.00	1.00	DOOR & FRAME PAINTER

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### UNIT B6 (quantities and amounts below reflect a single build of this typical area)

Condition	Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
	PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
	PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
24	03 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 3 EA				
	PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	2.40	1.00	MISCELLANEOUS TRIM PAINTER
	PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	2.40	1.00	MISCELLANEOUS TRIM PAINTER
	PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
	PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
25	05 TYPECC UNIT DBL.WOOD DOOR FRAME & DOOR PTD., 7' 0", 1 EA				
	PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
	PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
	PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
	PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
	PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
	PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
32	02 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 4 EA				
	PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
	PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
	PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	2.13	1.00	MISCELLANEOUS TRIM PAINTER
	PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	2.13	1.00	MISCELLANEOUS TRIM PAINTER

### (unassigned)

Condition	Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
48	S & V SHOE MOULD WOOD TRIM LF, , 12139 LF				
	STAIN - Apply Stain, WOODCLASSICS INTERIOR OIL STAIN	187.50 LF	64.74	1.00	INTERIOR TRIM PAINTER
	STAIN - Apply Stain, WOODCLASSICS SAND & SEALER	187.50 LF	64.74	1.00	INTERIOR TRIM PAINTER
	STAIN - Apply Stain, WOODCLASSICS WB POLYURETHANE VARNISH	187.50 LF	64.74	1.00	INTERIOR TRIM PAINTER

### BASEMENT

Condition	Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
16	11'4" CONCRETE LES WALLS, 11' 4", 612 SF				
	PRIME - Apply Primer, PROGREEN LOW VOC PRIMER	375.00 SF	1.63	1.00	INTERIOR WALLS PAINTER
	PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	375.00 SF	1.63	1.00	INTERIOR WALLS PAINTER
	PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	375.00 SF	1.63	1.00	INTERIOR WALLS PAINTER

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### BASEMENT

#### Floor 1

Condition	Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
1	PUBLIC AREA DW CLG. PTD. FLAT, , 1373 SF				
	PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER	375.00 SF	3.66	1.00	INTERIOR CEILING PAINTER
	PAINT - Apply Finish Paint, PREPRITE PROMAR 200 PRIMER	375.00 SF	3.66	1.00	INTERIOR CEILING PAINTER
	PAINT - Apply Finish Paint, PREPRITE PROMAR 200 PRIMER	375.00 SF	3.66	1.00	INTERIOR CEILING PAINTER
2	UNIT WOOD BASE PTD., 6", 4124 LF				
	PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	150.00 LF	27.50	1.00	INTERIOR PAINTER
	PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	27.50	1.00	INTERIOR PAINTER
	PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	27.50	1.00	INTERIOR PAINTER
8	10'4" DW WALLS LES, 10' 4", 1016 SF				
	PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	375.00 each	2.71	1.00	INTERIOR WALLS PAINTER
	PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	2.71	1.00	INTERIOR WALLS PAINTER
	PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	2.71	1.00	INTERIOR WALLS PAINTER
9	9' DW WALLS LES, 9' 0", 1862 SF				
	PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	375.00 each	4.97	1.00	INTERIOR WALLS PAINTER
	PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	4.97	1.00	INTERIOR WALLS PAINTER
	PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	4.97	1.00	INTERIOR WALLS PAINTER
10	10'4"CMU WALLS PTD., 10' 4", 1311 SF				
	FILLERS - BLOCK FILLER, PREPRITE FLAT BLOCKFILLER ( 1' x 1' )	312.50 each	4.19	1.00	INTERIOR WALLS PAINTER
	PAINT - Apply Finish Paint, PROGREEN 200 LOW COC LATEX SEMIGLOSS	312.50 SF	4.19	1.00	INTERIOR WALLS PAINTER
	PAINT - Apply Finish Paint, PROGREEN 200 LOW COC LATEX SEMIGLOSS	312.50 SF	4.19	1.00	INTERIOR WALLS PAINTER
12	UNIT DW CLG. PTD. FLAT, , 25643 SF				
	PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER	400.00 SF	64.11	1.00	INTERIOR CEILING PAINTER
	PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	64.11	1.00	INTERIOR CEILING PAINTER
	PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	64.11	1.00	INTERIOR CEILING PAINTER
13	9'1" UNIT BATH DW WALLS LSG, 9' 1", 5631 SF				
	PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	14.08	1.00	INTERIOR WALLS PAINTER
	PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	14.08	1.00	INTERIOR WALLS PAINTER
	PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	14.08	1.00	INTERIOR WALLS PAINTER
14	9'1" UNIT DW WALLS LES, 9' 1", 37458 SF				



# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### Floor 1

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	93.65	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	93.65	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	93.65	1.00	INTERIOR WALLS PAINTER
17 10'4"VWC 1, 10' 4", 1481 SF OWNER FURNISHED VWC MATERIAL				
VWC SIZE - SIZE WALLS FOR VWC, PREPRITE PREWALLCOVERING PRIMER ( 1' x 1' )	437.50 each	3.39	1.00	LABOR VWC
VWC HANG - HANG VINYL WALLCOVERING, 3'	5.02 each	23.60	1.00	VINYL HANGER
18 PUBLIC AREA WOOD BASE PTD., 6", 143 LF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	75.00 LF	1.91	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	75.00 LF	1.91	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	75.00 LF	1.91	1.00	INTERIOR PAINTER
21 01 TYPE A UNIT ENTRY HM DOOR FRAME & WOOD DOOR PTD., 7' 0", 8 EA				
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	8.00	1.00	DOOR & FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	5.33	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	5.33	1.00	MISCELLANEOUS TRIM PAINTER
22 ACCESS PANEL, 7' 0", 7 EA				
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	2.24	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	2.24	1.00	MISCELLANEOUS TRIM PAINTER
23 09 TYPE BB UNIT DBL.WOOD DOOR FRAME & DBL. WOOD DOOR PTD., 7' 0", 2 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT. LATEX PRIMER SEALER	1.25 EA	1.60	1.00	WOOD DOOR/FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	1.60	1.00	WOOD DOOR/FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
24 03 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 22 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT. LATEX PRIMER SEALER	1.25 EA	17.60	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	17.60	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	11.73	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	11.73	1.00	MISCELLANEOUS TRIM PAINTER
25 05 TYPECC UNIT DBL.WOOD DOOR FRAME & DOOR PTD., 7' 0", 7 EA				

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### Floor 1

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	5.60	1.00	WOOD DOOR/FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	5.60	1.00	WOOD DOOR/FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	4.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	4.67	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	4.67	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	4.67	1.00	MISCELLANEOUS TRIM PAINTER
26 06 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 3 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	2.40	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	2.40	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
28 04 UNIT TYPE C WOOD FRAME & WOOD DOOR PTD., 7' 0", 2 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	1.33	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	1.33	1.00	MISCELLANEOUS TRIM PAINTER
29 08 UNIT TYPE BB DBL. WOOD FRAME & DBL. WOOD DOOR PTD., 7' 0", 1 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
31 07 UNIT TYPE B WOOD FRAME & WOOD DOOR PTD., 7' 0", 6 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	4.80	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	4.80	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
32 02 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 30 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	24.00	1.00	MISCELLANEOUS TRIM PAINTER

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### Floor 1

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	24.00	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	16.00	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	16.00	1.00	MISCELLANEOUS TRIM PAINTER
44 4' UNIT DW WALLS LES, 4' 0", 127 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	0.32	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	0.32	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	0.32	1.00	INTERIOR WALLS PAINTER

### Floor 2

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
1 PUBLIC AREA DW CLG. PTD. FLAT, , 701 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER	375.00 SF	1.87	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PREPRITE PROMAR 200 PRIMER	375.00 SF	1.87	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PREPRITE PROMAR 200 PRIMER	375.00 SF	1.87	1.00	INTERIOR CEILING PAINTER
2 UNIT WOOD BASE PTD., 6", 4008 LF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	150.00 LF	26.73	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	26.73	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	26.73	1.00	INTERIOR PAINTER
9 9' DW WALLS LES, 9' 0", 2261 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	375.00 each	6.03	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	6.03	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	6.03	1.00	INTERIOR WALLS PAINTER
12 UNIT DW CLG. PTD. FLAT, , 23428 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER	400.00 SF	58.57	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	58.57	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	58.57	1.00	INTERIOR CEILING PAINTER
13 9'1" UNIT BATH DW WALLS LSG, 9' 1", 5513 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	13.78	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	13.78	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	13.78	1.00	INTERIOR WALLS PAINTER
14 9'1" UNIT DW WALLS LES, 9' 1", 37140 SF				

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### Floor 2

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	92.85	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	92.85	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	92.85	1.00	INTERIOR WALLS PAINTER
18 PUBLIC AREA WOOD BASE PTD., 6", 27 LF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	75.00 LF	0.36	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	75.00 LF	0.36	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	75.00 LF	0.36	1.00	INTERIOR PAINTER
19 9'CMU WALLS PTD., 9' 0", 957 SF				
FILLERS - BLOCK FILLER, PREPRITE FLAT BLOCKFILLER ( 1' x 1' )	312.50 each	3.06	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW COC LATEX SEMIGLOSS	312.50 SF	3.06	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW COC LATEX SEMIGLOSS	312.50 SF	3.06	1.00	INTERIOR WALLS PAINTER
20 9'VWC 1, 9' 0", 241 SF				
OWNER FURNISHED VWC MATERIAL				
VWC SIZE - SIZE WALLS FOR VWC, PREPRITE PREWALLCOVERING PRIMER ( 1' x 1' )	437.50 each	0.55	1.00	LABOR VWC
VWC HANG - HANG VINYL WALLCOVERING, 3'	4.96 each	3.88	1.00	VINYL HANGER
21 01 TYPE A UNIT ENTRY HM DOOR FRAME & WOOD DOOR PTD., 7' 0", 9 EA				
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	9.00	1.00	DOOR & FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	6.00	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	6.00	1.00	MISCELLANEOUS TRIM PAINTER
22 ACCESS PANEL, 7' 0", 8 EA				
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	2.56	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	2.56	1.00	MISCELLANEOUS TRIM PAINTER
23 09 TYPE BB UNIT DBL.WOOD DOOR FRAME & DBL. WOOD DOOR PTD., 7' 0", 2 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT. LATEX PRIMER SEALER	1.25 EA	1.60	1.00	WOOD DOOR/FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	1.60	1.00	WOOD DOOR/FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
24 03 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 26 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT. LATEX PRIMER SEALER	1.25 EA	20.80	1.00	MISCELLANEOUS TRIM PAINTER

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### Floor 2

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	20.80	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	13.87	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	13.87	1.00	MISCELLANEOUS TRIM PAINTER
25 05 TYPECC UNIT DBL.WOOD DOOR FRAME & DOOR PTD., 7' 0", 8 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	6.40	1.00	WOOD DOOR/FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	6.40	1.00	WOOD DOOR/FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	5.33	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	5.33	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	5.33	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	5.33	1.00	MISCELLANEOUS TRIM PAINTER
26 06 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 4 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	2.13	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	2.13	1.00	MISCELLANEOUS TRIM PAINTER
28 04 UNIT TYPE C WOOD FRAME & WOOD DOOR PTD., 7' 0", 2 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	1.33	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	1.33	1.00	MISCELLANEOUS TRIM PAINTER
29 08 UNIT TYPE BB DBL. WOOD FRAME & DBL. WOOD DOOR PTD., 7' 0", 1 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
31 07 UNIT TYPE B WOOD FRAME & WOOD DOOR PTD., 7' 0", 6 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	4.80	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	4.80	1.00	MISCELLANEOUS TRIM PAINTER

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### Floor 2

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
32 02 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 33 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	26.40	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	26.40	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	17.60	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	17.60	1.00	MISCELLANEOUS TRIM PAINTER
44 4' UNIT DW WALLS LES, 4' 0", 150 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	0.37	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	0.37	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	0.37	1.00	INTERIOR WALLS PAINTER

### Floor 3

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
1 PUBLIC AREA DW CLG. PTD. FLAT, , 701 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER	375.00 SF	1.87	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PREPRITE PROMAR 200 PRIMER	375.00 SF	1.87	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PREPRITE PROMAR 200 PRIMER	375.00 SF	1.87	1.00	INTERIOR CEILING PAINTER
2 UNIT WOOD BASE PTD., 6", 4008 LF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	150.00 LF	26.73	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	26.73	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	150.00 LF	26.73	1.00	INTERIOR PAINTER
8 10'4" DW WALLS LES, 10' 4", 323 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	375.00 each	0.86	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	0.86	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	0.86	1.00	INTERIOR WALLS PAINTER
9 9' DW WALLS LES, 9' 0", 1979 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	375.00 each	5.28	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	5.28	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	5.28	1.00	INTERIOR WALLS PAINTER
12 UNIT DW CLG. PTD. FLAT, , 23428 SF				

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### Floor 3

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER	400.00 SF	58.57	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	58.57	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	400.00 SF	58.57	1.00	INTERIOR CEILING PAINTER
13 9'1" UNIT BATH DW WALLS LSG, 9' 1", 5513 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	13.78	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	13.78	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX SEMIGLOSS	400.00 SF	13.78	1.00	INTERIOR WALLS PAINTER
14 9'1" UNIT DW WALLS LES, 9' 1", 37140 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	92.85	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	92.85	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	92.85	1.00	INTERIOR WALLS PAINTER
18 PUBLIC AREA WOOD BASE PTD., 6", 27 LF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	75.00 LF	0.36	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	75.00 LF	0.36	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	75.00 LF	0.36	1.00	INTERIOR PAINTER
19 9'CMU WALLS PTD., 9' 0", 961 SF				
FILLERS - BLOCK FILLER, PREPRITE FLAT BLOCKFILLER ( 1' x 1' )	312.50 each	3.07	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW COC LATEX SEMIGLOSS	312.50 SF	3.07	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW COC LATEX SEMIGLOSS	312.50 SF	3.07	1.00	INTERIOR WALLS PAINTER
20 9'VWC 1, 9' 0", 243 SF OWNER FURNISHED VWC MATERIAL				
VWC SIZE - SIZE WALLS FOR VWC, PREPRITE PREWALLCOVERING PRIMER ( 1' x 1' )	437.50 each	0.56	1.00	LABOR VWC
VWC HANG - HANG VINYL WALLCOVERING, 3'	4.96 each	3.92	1.00	VINYL HANGER
21 01 TYPE A UNIT ENTRY HM DOOR FRAME & WOOD DOOR PTD., 7' 0", 9 EA				
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	9.00	1.00	DOOR & FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	6.00	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	6.00	1.00	MISCELLANEOUS TRIM PAINTER
22 ACCESS PANEL, 7' 0", 8 EA				
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	2.56	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	3.13 EA	2.56	1.00	MISCELLANEOUS TRIM PAINTER
23 09 TYPE BB UNIT DBL.WOOD DOOR FRAME & DBL. WOOD DOOR PTD., 7' 0", 2 EA				

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### Floor 3

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	1.60	1.00	WOOD DOOR/FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	1.60	1.00	WOOD DOOR/FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	1.07	1.00	MISCELLANEOUS TRIM PAINTER
24 03 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 26 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	20.80	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	20.80	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	13.87	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	13.87	1.00	MISCELLANEOUS TRIM PAINTER
25 05 TYPECC UNIT DBL.WOOD DOOR FRAME & DOOR PTD., 7' 0", 8 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	6.40	1.00	WOOD DOOR/FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	6.40	1.00	WOOD DOOR/FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	5.33	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	5.33	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	5.33	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	5.33	1.00	MISCELLANEOUS TRIM PAINTER
26 06 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 4 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	2.13	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	2.13	1.00	MISCELLANEOUS TRIM PAINTER
28 04 UNIT TYPE C WOOD FRAME & WOOD DOOR PTD., 7' 0", 2 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	1.60	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	1.33	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	1.33	1.00	MISCELLANEOUS TRIM PAINTER
29 08 UNIT TYPE BB DBL. WOOD FRAME & DBL. WOOD DOOR PTD., 7' 0", 1 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER



# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### Floor 3

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	0.80	1.00	WOOD DOOR/FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	MISCELLANEOUS TRIM PAINTER
31 07 UNIT TYPE B WOOD FRAME & WOOD DOOR PTD., 7' 0", 6 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	4.80	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	4.80	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	3.20	1.00	MISCELLANEOUS TRIM PAINTER
32 02 TYPE B UNIT WOOD DOOR FRAME & WOOD DOOR PTD., 7' 0", 33 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER SEALER	1.25 EA	26.40	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.25 EA	26.40	1.00	MISCELLANEOUS TRIM PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.88 EA	17.60	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.88 EA	17.60	1.00	MISCELLANEOUS TRIM PAINTER
44 4' UNIT DW WALLS LES, 4' 0", 150 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	400.00 each	0.37	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	0.37	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	400.00 SF	0.37	1.00	INTERIOR WALLS PAINTER

### PUBLIC AREA DOORS/FRAMES

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
37 TYPE B HM DOOR/HM FRAME, 7' 0", 1 EA				
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	1.00	1.00	DOOR & FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	DOOR & FRAME PAINTER
40 TYPE E HM DOOR & DOOR FRAME PTD., 7' 0", 10 EA				
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	10.00	1.00	DOOR & FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.88 EA	5.33	1.00	DOOR & FRAME PAINTER
41 TYPE EE DBL. HM FRAME DBL. HM DOORS PTD., 7' 0", 1 EA				
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	0.88 EA	1.14	1.00	DOOR & FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	DOOR & FRAME PAINTER

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### PUBLIC AREA DOORS/FRAMES

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.88 EA	0.53	1.00	DOOR & FRAME PAINTER
42 TYPE D HM DOOR & DOOR FRAME PTD., 7' 0", 7 EA				
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	7.00	1.00	DOOR & FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.63 EA	4.31	1.00	DOOR & FRAME PAINTER
43 TYPE GG DBL. HM FRAME DBL.WD. DOORS PTD., 7' 0", 1 EA				
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	0.88 EA	1.14	1.00	DOOR & FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	DOOR & FRAME PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.50 EA	0.67	1.00	DOOR & FRAME PAINTER

### EXTERIOR ELEVATIONS

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
46 EXTERIOR TRIM PAINT LF, , 5668 LF				
PRIME - Apply Primer, A-100 LATEX PRIMER	62.50 LF	90.68	1.00	EXTERIOR PAINTER
PAINT - Apply Finish Paint, A-100 LATEX FLAT	68.75 LF	82.44	1.00	EXTERIOR PAINTER
PAINT - Apply Finish Paint, A-100 LATEX FLAT	75.00 LF	75.57	1.00	EXTERIOR PAINTER
47 LINTELS, , 190 LF				
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	17.50 LF	10.85	1.00	EXTERIOR PAINTER

### INTERIOR WINDOWS & WINDOW TRIM

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
3 WOOD WINDOW SILLS & APRON PTD., , 689 LF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	43.75 LF	15.75	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMIGLOSS	50.00 LF	13.79	1.00	INTERIOR TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMIGLOSS	56.25 LF	12.25	1.00	INTERIOR TRIM PAINTER
11 INTERIOR WD. WINDOW TRIM PTD., , 3196 LF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	93.75 LF	34.09	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMI GLOSS	93.75 LF	34.09	1.00	INTERIOR TRIM PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMI GLOSS	93.75 LF	34.09	1.00	INTERIOR TRIM PAINTER
45 WOOD WINDOWS PTD., , 235 EA				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER SEALER	0.88 EA	268.57	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMIGLOSS	0.88 EA	268.57	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMIGLOSS	0.88 EA	268.57	1.00	MISCELLANEOUS TRIM PAINTER

### STAIRS

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
4 RAILINGS (PICKET RAILING ), , 109 LF				

# Production Report

## 39 GREEN VILLAGE ROAD APTS.

Bid No. 43 - Job No. 6-19-14

### STAIRS

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	12.50 LF	8.70	1.00	INTERIOR TRIM PAINTER
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	12.50 LF	8.70	1.00	INTERIOR TRIM PAINTER
5 RAILINGS (1 RUNG PIPE RAILING ), , 108 LF				
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	46.88 LF	2.30	1.00	INTERIOR TRIM PAINTER
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	46.88 LF	2.30	1.00	INTERIOR TRIM PAINTER
7 INTERIOR STAIR FLIGHTS, , 10 EA				
PAINT - Apply Finish Paint	0.19 EA	53.33	1.00	INTERIOR PAINTER
15 EXT RAILINGS (1 RUNG PIPE RAILING ), , 19 LF				
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	50.00 LF	0.38	1.00	EXTERIOR TRIM PAINTER
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	50.00 LF	0.38	1.00	EXTERIOR TRIM PAINTER