

# Production Report

## DAVITA ( SANTA MARIA CA. )

Bid No. 75

Selected Sections: 09900 Painting, 09950 Wall Covering

Selected Typical Areas:

Selected Areas: (unassigned), FLOOR PLAN, EXTERIOR, DOORS/FRAMES, MISC. DETAILS, RCP

Estimator:

Job Class:

Wage Type: **Open**

Job Status: **PENDING**

Bid Date/Time: **8/12/2014 9:36:18 AM**

Plans Date: **7/22/2014**

### FLOOR PLAN

Condition	Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
1	4' DW WALLS LES, 4' 0", 471 SF				
	PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	375.00 each	1.26	1.00	INTERIOR WALLS PAINTER
	PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	1.26	1.00	INTERIOR WALLS PAINTER
	PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	1.26	1.00	INTERIOR WALLS PAINTER
2	10'6" DW WALLS LES, 10' 6", 131 SF				
	PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	375.00 each	0.35	1.00	INTERIOR WALLS PAINTER
	PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	0.35	1.00	INTERIOR WALLS PAINTER
	PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	0.35	1.00	INTERIOR WALLS PAINTER
12	10'6" VWC 2, 10' 6", 423 SF				
	WOLF GORDON 1-800-347-0550 METEOR STRIPE MOONLIGHT #G 7239284 COST \$20.50 LY				
	VWC SIZE - SIZE WALLS FOR VWC, PREPRITE PREWALLCOVERING PRIMER ( 1' x 1' )	437.50 each	0.97	1.00	LABOR VWC
	VWC HANG - HANG VINYL WALLCOVERING, 3'	2.50 each	13.50	1.00	VINYL HANGER
13	10'6" VWC 1, 10' 6", 927 SF				
	MDC 1-847-437-4000 STRING THEORY OBSERVATION #A4322/4527 COST \$13.95 LY				
	VWC SIZE - SIZE WALLS FOR VWC, PREPRITE PREWALLCOVERING PRIMER ( 1' x 1' )	437.50 each	2.12	1.00	LABOR VWC
	VWC HANG - HANG VINYL WALLCOVERING, 3'	2.67 each	29.25	1.00	VINYL HANGER
14	S & V WOOD CHAIR RAIL, , 100 LF				
	STAIN - Apply Stain, WOODCLASSICS INTERIOR OIL STAIN	56.25 LF	1.78	1.00	INTERIOR TRIM PAINTER
	STAIN - Apply Stain, WOODCLASSICS SAND & SEALER	56.25 LF	1.78	1.00	INTERIOR TRIM PAINTER
	STAIN - Apply Stain, WOODCLASSICS WB POLYURETHANE VARNISH	56.25 LF	1.78	1.00	INTERIOR TRIM PAINTER
15	5' VWC 2, 5' 0", 220 SF				
	WOLF GORDON 1-800-347-0550 METEOR STRIPE MOONLIGHT #G 7239284 COST \$20.50 LY				
	VWC SIZE - SIZE WALLS FOR VWC, PREPRITE PREWALLCOVERING PRIMER ( 1' x 1' )	437.50 each	0.50	1.00	LABOR VWC
	VWC HANG - HANG VINYL WALLCOVERING, 3'	2.47 each	7.12	1.00	VINYL HANGER
16	5' VWC 1, 5' 0", 760 SF				
	MDC 1-847-437-4000 STRING THEORY OBSERVATION #A4322/4527 COST \$13.95 LY				
	VWC SIZE - SIZE WALLS FOR VWC, PREPRITE PREWALLCOVERING PRIMER ( 1' x 1' )	437.50 each	1.74	1.00	LABOR VWC
	VWC HANG - HANG VINYL WALLCOVERING, 3'	2.67 each	24.00	1.00	VINYL HANGER
17	17'6" DW WALLS LES, 17' 6", 2198 SF				
	PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	312.50 each	7.03	1.00	INTERIOR WALLS PAINTER

# Production Report

## DAVITA ( SANTA MARIA CA. )

Bid No. 75

### FLOOR PLAN

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	312.50 SF	7.03	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	312.50 SF	7.03	1.00	INTERIOR WALLS PAINTER
18 3'6" DW WALLS LES, 3' 6", 80 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	375.00 each	0.21	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	0.21	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	0.21	1.00	INTERIOR WALLS PAINTER
19 10' DW WALLS LES, 10' 0", 2819 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	375.00 each	7.52	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	7.52	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	7.52	1.00	INTERIOR WALLS PAINTER
20 6'6" DW WALLS LES, 6' 6", 323 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	375.00 each	0.86	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	0.86	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	0.86	1.00	INTERIOR WALLS PAINTER
21 7' PLYWOOD PAINTED PER SF, 7' 0", 288 SF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	375.00 SF	0.77	1.00	INTERIOR TRIM PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMI GLOSS	312.50 SF	0.92	1.00	INTERIOR TRIM PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMI GLOSS	250.00 SF	1.15	1.00	INTERIOR TRIM PAINTER
22 3' DW WALLS LES, 3' 0", 123 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	375.00 each	0.33	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	0.33	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	0.33	1.00	INTERIOR WALLS PAINTER
23 6' DW WALLS LES, 6' 0", 324 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER ( 1' x 1' )	375.00 each	0.87	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	0.87	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	0.87	1.00	INTERIOR WALLS PAINTER

### EXTERIOR

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
3 EXT RAILINGS (PICKET RAILING ), , 65 LF				
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	28.13 LF	2.30	1.00	EXTERIOR TRIM PAINTER
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	28.13 LF	2.30	1.00	EXTERIOR TRIM PAINTER

# Production Report

## DAVITA ( SANTA MARIA CA. )

Bid No. 75

### EXTERIOR

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	28.13 LF	2.30	1.00	EXTERIOR TRIM PAINTER

### DOORS/FRAMES

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
----------------------	------------	------------	------	-----------

26 TYPE A HM DOOR FRAME & WOOD DOOR S & V, 7' 0", 11 EA

PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	11.00	1.00	DOOR & FRAME PAINTER
STAIN - Apply Stain, WOOD CLASSICS INTERIOR OIL STAIN	1.88 EA	5.87	1.00	MISCELLANEOUS TRIM PAINTER
STAIN - Apply Stain, WOOD CLASSICS SAND & SEALER	1.88 EA	5.87	1.00	MISCELLANEOUS TRIM PAINTER
STAIN - Apply Stain, WOOD CLASSICS WATERBORNE POLYURETHANE VARNISH	1.88 EA	5.87	1.00	MISCELLANEOUS TRIM PAINTER

27 TYPE A HM DOOR FRAME & WOOD DOOR PTD., 7' 0", 2 EA

PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMIGLOSS	1.00 EA	2.00	1.00	DOOR & FRAME PAINTER
PRIME - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	1.50 EA	1.33	1.00	MISCELLANEOUS TRIM PAINTER
PAINT - Apply Finish Paint, PROCLASSIC WATERBORNE ACRYLIC SEMI GLOSS	1.50 EA	1.33	1.00	MISCELLANEOUS TRIM PAINTER

28 TYPE B HM DOOR FRAME & WOOD DOOR S & V, 7' 0", 1 EA

PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	1.00	1.00	DOOR & FRAME PAINTER
STAIN - Apply Stain, WOOD CLASSICS INTERIOR OIL STAIN	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
STAIN - Apply Stain, WOOD CLASSICS SAND & SEALER	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER
STAIN - Apply Stain, WOOD CLASSICS WATERBORNE POLYURETHANE VARNISH	1.50 EA	0.67	1.00	MISCELLANEOUS TRIM PAINTER

29 TYPE C HM DOOR FRAME & WOOD DOOR S & V, 7' 0", 2 EA

PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	2.00	1.00	DOOR & FRAME PAINTER
STAIN - Apply Stain, WOOD CLASSICS INTERIOR OIL STAIN	1.50 EA	1.33	1.00	MISCELLANEOUS TRIM PAINTER
STAIN - Apply Stain, WOOD CLASSICS SAND & SEALER	1.50 EA	1.33	1.00	MISCELLANEOUS TRIM PAINTER
STAIN - Apply Stain, WOOD CLASSICS WATERBORNE POLYURETHANE VARNISH	1.50 EA	1.33	1.00	MISCELLANEOUS TRIM PAINTER

30 TYPE D HM DOOR FRAME & WOOD DOOR S & V, 7' 0", 4 EA

PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	1.00 EA	4.00	1.00	DOOR & FRAME PAINTER
STAIN - Apply Stain, WOOD CLASSICS INTERIOR OIL STAIN	1.50 EA	2.67	1.00	MISCELLANEOUS TRIM PAINTER
STAIN - Apply Stain, WOOD CLASSICS SAND & SEALER	1.50 EA	2.67	1.00	MISCELLANEOUS TRIM PAINTER
STAIN - Apply Stain, WOOD CLASSICS WATERBORNE POLYURETHANE VARNISH	1.50 EA	2.67	1.00	MISCELLANEOUS TRIM PAINTER

### MISC. DETAILS

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
----------------------	------------	------------	------	-----------

25 EXTERIOR LADDER, , 1 EA

PAINT - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	0.25 EA	4.00	1.00	INTERIOR PAINTER
---	---------	------	------	------------------

# Production Report

## DAVITA ( SANTA MARIA CA. )

Bid No. 75

### MISC. DETAILS

#### RCP

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
10 DW CLG. PTD. FLAT, , 621 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER	312.50 SF	1.99	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	312.50 SF	1.99	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	312.50 SF	1.99	1.00	INTERIOR CEILING PAINTER
24 3' DW SOFFIT FACE, 3' 0", 55 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER	250.00 SF	0.22	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	250.00 SF	0.22	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	250.00 SF	0.22	1.00	INTERIOR CEILING PAINTER