

Production Report

EAST ROCHESTER SCHOOL

Bid No. 39 - Job No. 4-16-14

Selected Sections: 02000 Misc. Bid Items, 09900 Painting

Selected Typical Areas:

Selected Areas: (unassigned), PHASE 1 DOORS/FRAMES, INTERIOR ELEVATIONS, PHASE 2 DOORS/FRAMES, STAIRS, PHASE 2 RCP, PHASE 1 LEVEL 1 RCP, PHASE 1 LEVEL 2 RCP, PHASE 1 FLOOR PLAN LEVEL 1, PHASE 1 FLOOR PLAN LEVEL 2, PHASE 2 FLOOR PLAN, EXTERIOR

Estimator:
Job Class:
Wage Type: **Open**

Job Status: **PENDING**
Bid Date/Time: **4/7/2014 12:00:00 PM**
Plans Date: **4/7/2014**

PHASE 1 DOORS/FRAMES

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
2 TYPE 1 HM DOOR FRAMES. PTD., 7' 0", 33 EA				
PAINT - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	3.00 EA	11.00	1.00	DOOR & FRAME PAINTER
PAINT - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	3.75 EA	8.80	1.00	DOOR & FRAME PAINTER
40 TYPE 2 HM DOOR FRAMES. PTD., 7' 0", 19 EA 49 LF X 29=1421				
PAINT - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	26.88 LF	34.64	1.00	EXTERIOR PAINTER
PAINT - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	26.88 LF	34.64	1.00	EXTERIOR PAINTER
41 TYPE 3 HM DOOR FRAMES. PTD., 7' 0", 4 EA 72 LF X 4=288				
PAINT - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	26.88 LF	10.72	1.00	EXTERIOR PAINTER
PAINT - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	26.88 LF	10.72	1.00	EXTERIOR PAINTER
45 HM DOOR, 7' 0", 4 EA				
PAINT - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	4.13 EA	0.97	1.00	DOOR & FRAME PAINTER
PAINT - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	5.00 EA	0.80	1.00	DOOR & FRAME PAINTER

INTERIOR ELEVATIONS

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
46 METAL STRUCTURAL BEAMS PRIME & PAINT PER LF, , 38 LF				
PRIME - Apply Primer, PROINDUSTRIAL PROCRYL UNIVERSAL ACRYLIC PRIMER	28.75 LF	1.31	1.00	EXTERIOR PAINTER
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	37.50 LF	1.00	1.00	EXTERIOR PAINTER
47 S & V WOOD TRIM, , 231 LF				
STAIN - Apply Stain, WOODCLASSICS INTERIOR OIL STAIN	78.00 LF	2.96	1.00	INTERIOR TRIM PAINTER
STAIN - Apply Stain, WOODCLASSICS SAND & SEALER	105.00 LF	2.20	1.00	INTERIOR TRIM PAINTER
STAIN - Apply Stain, WOODCLASSICS WB POLYURETHANE VARNISH	135.00 LF	1.71	1.00	INTERIOR TRIM PAINTER

PHASE 2 DOORS/FRAMES

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
2 TYPE 1 HM DOOR FRAMES. PTD., 7' 0", 15 EA				

Production Report

EAST ROCHESTER SCHOOL

Bid No. 39 - Job No. 4-16-14

PHASE 2 DOORS/FRAMES

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PAINT - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	3.00 EA	5.00	1.00	DOOR & FRAME PAINTER
PAINT - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	3.75 EA	4.00	1.00	DOOR & FRAME PAINTER
40 TYPE 2 HM DOOR FRAMES. PTD., 7' 0", 10 EA 49 LF X 29=1421				
PAINT - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	26.88 LF	18.23	1.00	EXTERIOR PAINTER
PAINT - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	26.88 LF	18.23	1.00	EXTERIOR PAINTER
42 TYPE 4 HM DOOR FRAMES. PTD., 7' 0", 2 EA 31 LF X 2 =62				
PAINT - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	26.88 LF	2.31	1.00	EXTERIOR PAINTER
PAINT - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	26.88 LF	2.31	1.00	EXTERIOR PAINTER
45 HM DOOR, 7' 0", 2 EA				
PAINT - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	4.13 EA	0.48	1.00	DOOR & FRAME PAINTER
PAINT - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	5.00 EA	0.40	1.00	DOOR & FRAME PAINTER

STAIRS

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
37 RAILINGS (1 RUNG PIPE RAILING), , 73 LF				
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	46.88 LF	1.57	1.00	INTERIOR TRIM PAINTER
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	46.88 LF	1.57	1.00	INTERIOR TRIM PAINTER
38 INTERIOR STAIR FLIGHTS, , 5 EA				
PAINT - Apply Finish Paint	0.19 EA	26.67	1.00	INTERIOR PAINTER
39 RAILINGS (PICKET RAILING), , 76 LF				
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	12.50 LF	6.08	1.00	INTERIOR TRIM PAINTER
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	12.50 LF	6.08	1.00	INTERIOR TRIM PAINTER

PHASE 2 RCP

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
1 DW CLG. PTD. FLAT, , 1262 SF				
PRIME - Apply Primer, HARMONY PRIMER	248.50 SF	5.08	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX FLAT	302.63 SF	4.17	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX FLAT	336.50 SF	3.75	1.00	INTERIOR CEILING PAINTER
11 EXP. CONST. CLG. W / WATERBORNE ACRYLIC DRYFALL, , 7516 SF				
PAINT - Apply Finish Paint, WATERBORNE ACRYLIC EGGSHELL (1' x 1')	295.00 each	25.48	1.00	EXPOSED CONSTR. CEILING PAINTER
33 3' DW SOFFIT FACE, 3' 0", 227 SF				
PRIME - Apply Primer, HARMONY PRIMER	248.50 SF	0.91	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX FLAT	302.63 SF	0.75	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX FLAT	336.50 SF	0.67	1.00	INTERIOR CEILING PAINTER
34 ACOUSTICAL GRID & TILE PAINTED, , 1224 SF				

Production Report

EAST ROCHESTER SCHOOL

Bid No. 39 - Job No. 4-16-14

PHASE 2 RCP

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PAINT - Apply Finish Paint, 1' x 1'	250.00 each	4.90	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, 1' x 1'	250.00 each	4.90	1.00	INTERIOR CEILING PAINTER
35 WD. TRIM PTD., , 257 LF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	77.25 LF	3.32	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMI GLOSS	106.13 LF	2.42	1.00	INTERIOR TRIM PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMI GLOSS	136.38 LF	1.88	1.00	INTERIOR TRIM PAINTER
36 EXP. CONST. CLG. JOIST & BEAM W / UNIGRIP DRYFALL, , 537 LF				
PAINT - Apply Finish Paint, DTM (1')	52.00 each	10.33	1.00	EXPOSED CONSTR. CEILING PAINTER
PREP - PREP FOR PAINTING	46.88 LF	22.91	1.00	INT. EXT. CUT LINE PAINTER
51 EXTERIOR SOFFIT PANEL PAINT SF, , 411 SF				
PRESSURE WASH - PRESSURE WASH, 1' x 1'	750.00 each	0.55	1.00	EXTERIOR PAINTER
PRIME - Apply Primer, A-100 LATEX PRIMER (1' x 1')	173.63 each	2.37	1.00	EXTERIOR TRIM PAINTER
PAINT - Apply Finish Paint, A-100 LATEX FLAT (1' x 1')	234.13 each	1.76	1.00	EXTERIOR TRIM PAINTER
PAINT - Apply Finish Paint, A-100 LATEX FLAT (1' x 1')	316.00 each	1.30	1.00	EXTERIOR TRIM PAINTER

PHASE 1 LEVEL 1 RCP

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
1 DW CLG. PTD. FLAT, , 535 SF				
PRIME - Apply Primer, HARMONY PRIMER	248.50 SF	2.15	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX FLAT	302.63 SF	1.77	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX FLAT	336.50 SF	1.59	1.00	INTERIOR CEILING PAINTER
6 1' DW SOFFIT FACE, 1' 0", 34 SF				
PRIME - Apply Primer, HARMONY PRIMER	248.50 SF	0.14	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX FLAT	302.63 SF	0.11	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX FLAT	336.50 SF	0.10	1.00	INTERIOR CEILING PAINTER
11 EXP. CONST. CLG. W / WATERBORNE ACRYLIC DRYFALL, , 1962 SF				
PAINT - Apply Finish Paint, WATERBORNE ACRYLIC EGGSHELL (1' x 1')	295.00 each	6.65	1.00	EXPOSED CONSTR. CEILING PAINTER
33 3' DW SOFFIT FACE, 3' 0", 924 SF				
PRIME - Apply Primer, HARMONY PRIMER	248.50 SF	3.72	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX FLAT	302.63 SF	3.05	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX FLAT	336.50 SF	2.75	1.00	INTERIOR CEILING PAINTER

PHASE 1 LEVEL 2 RCP

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
1 DW CLG. PTD. FLAT, , 367 SF				

Production Report

EAST ROCHESTER SCHOOL

Bid No. 39 - Job No. 4-16-14

PHASE 1 LEVEL 2 RCP

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PRIME - Apply Primer, HARMONY PRIMER	248.50 SF	1.48	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX FLAT	302.63 SF	1.21	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX FLAT	336.50 SF	1.09	1.00	INTERIOR CEILING PAINTER
6 1' DW SOFFIT FACE, 1' 0", 20 SF				
PRIME - Apply Primer, HARMONY PRIMER	248.50 SF	0.08	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX FLAT	302.63 SF	0.07	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX FLAT	336.50 SF	0.06	1.00	INTERIOR CEILING PAINTER
11 EXP. CONST. CLG. W / WATERBORNE ACRYLIC DRYFALL, , 1920 SF				
PAINT - Apply Finish Paint, WATERBORNE ACRYLIC EGGSHELL (1' x 1')	295.00 each	6.51	1.00	EXPOSED CONSTR. CEILING PAINTER
33 3' DW SOFFIT FACE, 3' 0", 900 SF				
PRIME - Apply Primer, HARMONY PRIMER	248.50 SF	3.62	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX FLAT	302.63 SF	2.97	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX FLAT	336.50 SF	2.67	1.00	INTERIOR CEILING PAINTER
34 ACOUSTICAL GRID & TILE PAINTED, , 442 SF				
PAINT - Apply Finish Paint, 1' x 1'	250.00 each	1.77	1.00	INTERIOR CEILING PAINTER
PAINT - Apply Finish Paint, 1' x 1'	250.00 each	1.77	1.00	INTERIOR CEILING PAINTER
35 WD. TRIM PTD., , 193 LF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	77.25 LF	2.50	1.00	INTERIOR PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMI GLOSS	106.13 LF	1.82	1.00	INTERIOR TRIM PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LATEX SEMI GLOSS	136.38 LF	1.42	1.00	INTERIOR TRIM PAINTER

PHASE 1 FLOOR PLAN LEVEL 1

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
3 S & V WOOD TRIM, , 134 LF				
STAIN - Apply Stain, WOODCLASSICS INTERIOR OIL STAIN	78.00 LF	1.71	1.00	INTERIOR TRIM PAINTER
STAIN - Apply Stain, WOODCLASSICS SAND & SEALER	105.00 LF	1.27	1.00	INTERIOR TRIM PAINTER
STAIN - Apply Stain, WOODCLASSICS WB POLYURETHANE VARNISH	135.00 LF	0.99	1.00	INTERIOR TRIM PAINTER
4 EXT RAILINGS (7 RUNG PIPE RAILING), , 21 LF				
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	17.50 LF	1.18	1.00	EXTERIOR TRIM PAINTER
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	17.50 LF	1.18	1.00	EXTERIOR TRIM PAINTER
9 CONC. FLOORS SEALED, , 61 SF USING EUCO DIAMOND HARDFLOOR SEALER.				
PREP - PREP FOR PAINTING	1,000.00 SF	0.06	1.00	FLOOR PAINTER
PREP - PREP FOR PAINTING, 1' x 1'	500.00 each	0.12	1.00	FLOOR PAINTER
FLOOR COATING - FLOOR COATINGS, CLEAR 23 (1' x 1')	312.50 each	0.19	1.00	FLOOR PAINTER
13 14'8"DW WALLS EPOXY, 14' 8", 3167 SF				

Production Report

EAST ROCHESTER SCHOOL

Bid No. 39 - Job No. 4-16-14

PHASE 1 FLOOR PLAN LEVEL 1

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER (1' x 1')	306.38 each	10.34	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	390.13 SF	8.12	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	457.13 SF	6.93	1.00	INTERIOR WALLS PAINTER
14 10' DW WALLS EPOXY, 10' 0", 3566 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER (1' x 1')	306.38 each	11.64	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	390.13 SF	9.14	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	457.13 SF	7.80	1.00	INTERIOR WALLS PAINTER
15 10' DW WALLS LES, 10' 0", 11473 SF				
PRIME - Apply Primer, HARMONY PRIMER (1' x 1')	306.38 each	37.45	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	390.13 SF	29.41	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	457.13 SF	25.10	1.00	INTERIOR WALLS PAINTER
16 9' DW WALLS EPOXY, 9' 0", 1948 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER (1' x 1')	306.38 each	6.36	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	390.13 SF	4.99	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	457.13 SF	4.26	1.00	INTERIOR WALLS PAINTER
17 8' DW WALLS EPOXY, 8' 0", 282 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER (1' x 1')	306.38 each	0.92	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	390.13 SF	0.72	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	457.13 SF	0.62	1.00	INTERIOR WALLS PAINTER
18 11'6" DW WALLS LES, 11' 6", 1266 SF				
PRIME - Apply Primer, HARMONY PRIMER (1' x 1')	306.38 each	4.13	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	390.13 SF	3.25	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	457.13 SF	2.77	1.00	INTERIOR WALLS PAINTER
19 14'8" DW WALLS LES, 14' 8", 1450 SF				
PRIME - Apply Primer, HARMONY PRIMER (1' x 1')	306.38 each	4.73	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	390.13 SF	3.72	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	457.13 SF	3.17	1.00	INTERIOR WALLS PAINTER
20 8' DW WALLS LES, 8' 0", 252 SF				
PRIME - Apply Primer, HARMONY PRIMER (1' x 1')	306.38 each	0.82	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	390.13 SF	0.65	1.00	INTERIOR WALLS PAINTER

Production Report

EAST ROCHESTER SCHOOL

Bid No. 39 - Job No. 4-16-14

PHASE 1 FLOOR PLAN LEVEL 1

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	457.13 SF	0.55	1.00	INTERIOR WALLS PAINTER
32 14'8" CMU WALLS LES, 14' 8", 56 SF				
FILLERS - BLOCK FILLER, PREPRITE FLAT BLOCKFILLER (1' x 1')	247.00 each	0.23	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	279.75 SF	0.20	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	370.38 SF	0.15	1.00	INTERIOR WALLS PAINTER
48 14'8" EXISTING CMU WALLS LES, 14' 8", 1481 SF				
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	215.25 SF	6.88	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	285.00 SF	5.20	1.00	INTERIOR WALLS PAINTER

PHASE 1 FLOOR PLAN LEVEL 2

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
14 10' DW WALLS EPOXY, 10' 0", 4746 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER (1' x 1')	306.38 each	15.49	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	390.13 SF	12.16	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	457.13 SF	10.38	1.00	INTERIOR WALLS PAINTER
15 10' DW WALLS LES, 10' 0", 12554 SF				
PRIME - Apply Primer, HARMONY PRIMER (1' x 1')	306.38 each	40.98	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	390.13 SF	32.18	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	457.13 SF	27.46	1.00	INTERIOR WALLS PAINTER
16 9' DW WALLS EPOXY, 9' 0", 1471 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER (1' x 1')	306.38 each	4.80	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	390.13 SF	3.77	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	457.13 SF	3.22	1.00	INTERIOR WALLS PAINTER
17 8' DW WALLS EPOXY, 8' 0", 282 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER (1' x 1')	306.38 each	0.92	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	390.13 SF	0.72	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	457.13 SF	0.62	1.00	INTERIOR WALLS PAINTER
18 11'6" DW WALLS LES, 11' 6", 1266 SF				
PRIME - Apply Primer, HARMONY PRIMER (1' x 1')	306.38 each	4.13	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	390.13 SF	3.25	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	457.13 SF	2.77	1.00	INTERIOR WALLS PAINTER
43 14'4"DW WALLS EPOXY, 14' 4", 2080 SF				

Production Report

EAST ROCHESTER SCHOOL

Bid No. 39 - Job No. 4-16-14

PHASE 1 FLOOR PLAN LEVEL 2

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER (1' x 1')	306.38 each	6.79	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	390.13 SF	5.33	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	457.13 SF	4.55	1.00	INTERIOR WALLS PAINTER
44 14'4"DW WALLS LES, 14' 4", 1359 SF				
PRIME - Apply Primer, HARMONY PRIMER (1' x 1')	306.38 each	4.44	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	390.13 SF	3.48	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	457.13 SF	2.97	1.00	INTERIOR WALLS PAINTER

PHASE 2 FLOOR PLAN

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
7 18'8" EXISTING CMU WALLS LES, 18' 8", 7476 SF				
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	215.25 SF	34.73	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	285.00 SF	26.23	1.00	INTERIOR WALLS PAINTER
8 9'DW WALLS LES, 9' 0", 4823 SF				
PRIME - Apply Primer, HARMONY PRIMER (1' x 1')	306.38 each	15.74	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	390.13 SF	12.36	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	457.13 SF	10.55	1.00	INTERIOR WALLS PAINTER
10 CONCRETE FLOORS EPOXY, , 131 SF				
1 COAT SW AMORSEAL WB EPOXY PRIMER/SEALER				
2ND COAT SW AMORSEAL 700HS WATER BASED EPOXY				
PREP - PREP FOR PAINTING	1,000.00 SF	0.13	1.00	FLOOR PAINTER
PREP - PREP FOR PAINTING, 1' x 1'	500.00 each	0.26	1.00	FLOOR PAINTER
FLOOR COATING - FLOOR COATINGS, S-W AMORSEAL WB EPOXY PRIMER/SEALER (KIT PART A & B) (1' x 1')	375.00 each	0.35	1.00	FLOOR PAINTER
FLOOR COATING - FLOOR COATINGS, S-W AMORSEAL 700HS WATER BASED EPOXY (KIT PART A & B) (1' x 1')	375.00 each	0.35	1.00	FLOOR PAINTER
15 10' DW WALLS LES, 10' 0", 460 SF				
PRIME - Apply Primer, HARMONY PRIMER (1' x 1')	306.38 each	1.50	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	390.13 SF	1.18	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	457.13 SF	1.01	1.00	INTERIOR WALLS PAINTER
16 9' DW WALLS EPOXY, 9' 0", 1044 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER (1' x 1')	306.38 each	3.41	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	390.13 SF	2.68	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	457.13 SF	2.28	1.00	INTERIOR WALLS PAINTER
21 8'8" EXISTING WALLS EPOXY, 8' 8", 207 SF				

Production Report

EAST ROCHESTER SCHOOL

Bid No. 39 - Job No. 4-16-14

PHASE 2 FLOOR PLAN

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PREP - PREP FOR PAINTING	1,000.00 SF	0.21	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	238.00 SF	0.87	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	314.50 SF	0.66	1.00	INTERIOR WALLS PAINTER
22 8'8" DW WALLS EPOXY, 8' 8", 56 SF				
PRIME - Apply Primer, PROGREEN 200 LOW VOC PRIMER (1' x 1')	306.38 each	0.18	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	390.13 SF	0.14	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, WB CATALYZED EPOXY	457.13 SF	0.12	1.00	INTERIOR WALLS PAINTER
23 8'8" DW WALLS LES, 8' 8", 277 SF				
PRIME - Apply Primer, HARMONY PRIMER (1' x 1')	306.38 each	0.90	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	390.13 SF	0.71	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	457.13 SF	0.61	1.00	INTERIOR WALLS PAINTER
24 8'8" EXISTING DW WALLS LES, 8' 8", 59 SF				
PREP - PREP FOR PAINTING	1,000.00 SF	0.06	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	238.00 SF	0.25	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	314.50 SF	0.19	1.00	INTERIOR WALLS PAINTER
25 16'7" EXISTING CMU WALLS LES, 16' 7", 1614 SF				
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	215.25 SF	7.50	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	285.00 SF	5.66	1.00	INTERIOR WALLS PAINTER
26 10' EXISTING CMU WALLS LES, 10' 0", 6620 SF				
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	215.25 SF	30.75	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	285.00 SF	23.23	1.00	INTERIOR WALLS PAINTER
27 17'7" DW WALLS LES, 17' 7", 9017 SF				
PRIME - Apply Primer, HARMONY PRIMER (1' x 1')	306.38 each	29.43	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	390.13 SF	23.11	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	457.13 SF	19.73	1.00	INTERIOR WALLS PAINTER
28 17'7" EXISTING GLAZED CMU WALLS LES, 17' 7", 2194 SF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER SEALER (1' x 1')	312.50 each	7.02	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	215.25 SF	10.19	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	285.00 SF	7.70	1.00	INTERIOR WALLS PAINTER
29 9' EXISTING CMU WALLS LES, 9' 0", 131 SF				

Production Report

EAST ROCHESTER SCHOOL

Bid No. 39 - Job No. 4-16-14

PHASE 2 FLOOR PLAN

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	215.25 SF	0.61	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	285.00 SF	0.46	1.00	INTERIOR WALLS PAINTER
30 10' DW WALLS LES, 10' 0", 2341 SF				
PRIME - Apply Primer, HARMONY PRIMER (1' x 1')	306.38 each	7.64	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	390.13 SF	6.00	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	457.13 SF	5.12	1.00	INTERIOR WALLS PAINTER
31 10'DW WALLS LES, 10' 0", 81 SF				
PRIME - Apply Primer, HARMONY PRIMER (1' x 1')	306.38 each	0.26	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	390.13 SF	0.21	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	457.13 SF	0.18	1.00	INTERIOR WALLS PAINTER
49 8'8" EXISTING KITCHEN GLAZED CMU WALLS LES, 8' 8", 1910 SF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER SEALER (1' x 1')	312.50 each	6.11	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	215.25 SF	8.87	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	285.00 SF	6.70	1.00	INTERIOR WALLS PAINTER
50 18'8" EXISTING GLAZED CMU WALLS LES, 18' 8", 1142 SF				
PRIME - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER SEALER (1' x 1')	312.50 each	3.65	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	215.25 SF	5.30	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, HARMONY LATEX EGGSHELL	285.00 SF	4.01	1.00	INTERIOR WALLS PAINTER

EXTERIOR

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
5 LINTELS, , 448 LF				
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	106.13 LF	4.22	1.00	EXTERIOR PAINTER
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	106.13 LF	4.22	1.00	EXTERIOR PAINTER
PAINT - Apply Finish Paint, INDUSTRIAL ENAMEL	146.75 LF	3.06	1.00	EXTERIOR PAINTER