

# Bid Summary

## PACSUN STORE

Bid No. 134

Selected Sections: 02000 Misc. Bid Items, 09900 Painting

Selected Typical Areas:

Selected Areas: (unassigned), FLOOR PLAN, RCP, INTERIOR ELEVATIONS, DOORS/FRAMES, BARACADE PLAN ELEVATION

Estimator:

Job Class:

Wage Type: **Open**

Job Status: **PENDING**

Bid Date/Time: **1/8/2015 3:16:43 PM**

Plans Date: **12/3/2014**

PAYROLL @ \$40.00

(unassigned)

Equipment	Quantity	Equipment	Unit Pricing			Total Price	Man Hours
			Lab.	Total			
15 FT. ELECTRIC SCISSOR LIFT WEEK	1.00 WEEK	325.00	0.00	325.00		325.00	0.00
Equipment & Labor Total:						<b>325.00</b>	<b>0.00</b>
(unassigned) Total:						<b>325.00</b>	<b>0.00</b>

### FLOOR PLAN

No.	Condition	Height	Quantity	Unit Pricing			Total Price	Man Hours
				Mat.	Lab.	Total		
2	HM DOOR & DOOR FRAME PTD.	7' 0"	3.00 EA	19.31	54.81	74.12 / EA	222.36	4.11
3	18'9" DW WALLS LES	18' 9"	3,628.13 SF	0.15	0.42	0.57 / SF	2,052.91	37.80
4	19' STL. COLUMNS PTD.	19' 0"	3.00 EA	17.85	91.43	109.28 / EA	327.84	6.86
8	4'6" DW PRIME ONLY	4' 6"	186.75 SF	0.15	0.42	0.57 / SF	105.67	1.95
9	WOOD BASE PTD.	6"	300.50 LF	0.17	2.22	2.39 / LF	718.72	16.70
11	CUT LINE		193.50 LF	0.00	1.00	1.00 / LF	193.50	4.84
14	WD. TRIM PTD.		333.58 LF	0.17	2.22	2.40 / LF	799.09	18.53
17	WD. DOOR PTD. & WD. FRAME PTD.	7' 0"	5.00 EA	16.94	84.29	101.23 / EA	506.15	10.54
19	12' DW WALLS LES	12' 0"	2,049.00 SF	0.15	0.42	0.57 / SF	1,159.39	21.35
20	4'6" DW WALLS EPOXY	4' 6"	129.00 SF	0.15	0.42	0.57 / SF	72.99	1.34
21	19' DW PRIME ONLY	19' 0"	2,758.17 SF	0.15	0.42	0.57 / SF	1,560.66	28.73
22	WD. SGL. FRAME PTD.	7' 0"	1.00 EA	8.52	71.95	80.46 / EA	80.46	1.80
Material & Labor Total:							7,799.74	154.54
FLOOR PLAN Total:							7,799.74	154.54

### RCP

No.	Condition	Height	Quantity	Unit Pricing			Total Price	Man Hours
				Mat.	Lab.	Total		
5	DW CLG. PTD. FLAT		242.39 SF	0.12	0.54	0.66 / SF	159.87	3.25
12	EXP. CONST. CLG. W / WATERBORNE ACRYLIC DRYFALL		3,172.57 SF	0.34	0.20	0.54 / SF	1,720.73	16.13
18	DW CLG. PTD. EPOXY		50.17 SF	0.12	0.54	0.66 / SF	33.09	0.67
Material & Labor Total:							1,913.69	20.05
RCP Total:							1,913.69	20.05

### INTERIOR ELEVATIONS

No.	Condition	Height	Quantity	Unit Pricing			Total Price	Man Hours
				Mat.	Lab.	Total		
1	AREA DW WALLS LES		313.51 SF	0.15	0.42	0.57 / SF	177.39	3.27
Material & Labor Total:							177.39	3.27
INTERIOR ELEVATIONS Total:							177.39	3.27

### BARACADE PLAN ELEVATION

			Unit Pricing				Man	
No.	Condition	Height	Quantity	Mat.	Lab.	Total	Hours	
1	AREA DW WALLS LES		511.72 SF	0.15	0.42	0.57 / SF	289.55	5.33
16	WD. DOOR PTD.	7' 0"	2.00 EA	8.42	42.15	50.57 / EA	101.14	2.11
Material & Labor Total:						390.69	7.44	

**Bid Summary**  
***PACSUN STORE***

Bid No. 134

BARACADE PLAN ELEVATION Total:	390.69	7.44
--------------------------------	--------	------

Grand Total:	\$10,606.51	185.29
--------------	-------------	--------