

Production Report

PACSUN STORE

Bid No. 134

Selected Sections: 02000 Misc. Bid Items, 09900 Painting

Selected Typical Areas:

Selected Areas: (unassigned), FLOOR PLAN, RCP, INTERIOR ELEVATIONS, DOORS/FRAMES, BARCADE PLAN ELEVATION

Estimator:

Job Class:

Wage Type: **Open**

Job Status: **PENDING**

Bid Date/Time: **1/8/2015 3:16:43 PM**

Plans Date: **12/3/2014**

PAYROLL @ \$40.00

09900 Painting

FLOOR PLAN

Condition Labor Code	Pcs./Days	Crew Days	Crew	Installer
2 HM DOOR & DOOR FRAME PTD., 7' 0", 3 EA				
100 - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	18.00 EA	0.17	1.00	DOOR & FRAME PAINTER
100 - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	23.00 EA	0.13	1.00	DOOR & FRAME PAINTER
100 - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	25.00 EA	0.12	1.00	DOOR & FRAME PAINTER
100 - Apply Finish Paint, DTM ACRYLIC SEMIGLOSS	31.00 EA	0.10	1.00	DOOR & FRAME PAINTER
3 18'9" DW WALLS LES, 18' 9", 3628 SF				
100 - Apply Primer, PROGREEN 200 LOW VOC PRIMER (1' x 1')	1,886.00 each	1.92	1.00	INTERIOR WALLS PAINTER
100 - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	2,401.00 SF	1.51	1.00	INTERIOR WALLS PAINTER
100 - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	2,813.00 SF	1.29	1.00	INTERIOR WALLS PAINTER
4 19' STL. COLUMNS PTD., 19' 0", 3 EA				
100 - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	7.00 EA	0.43	1.00	INTERIOR TRIM PAINTER
100 - Apply Finish Paint, PROINDUSTRIAL INDUSTRIAL ENAMEL	7.00 EA	0.43	1.00	INTERIOR TRIM PAINTER
8 4'6" DW PRIME ONLY, 4' 6", 187 SF				
100 - Apply Primer, PROGREEN 200 LOW VOC PRIMER (1' x 1')	1,886.00 each	0.10	1.00	INTERIOR WALLS PAINTER
100 - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	2,401.00 SF	0.08	1.00	INTERIOR WALLS PAINTER
100 - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	2,813.00 SF	0.07	1.00	INTERIOR WALLS PAINTER
9 WOOD BASE PTD., 6", 301 LF				
100 - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	400.00 LF	0.75	1.00	INTERIOR PAINTER
100 - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	450.00 LF	0.67	1.00	INTERIOR PAINTER
100 - Apply Finish Paint, PROGREEN 200 LATEX SEMIGLOSS	450.00 LF	0.67	1.00	INTERIOR PAINTER
11 CUT LINE, , 194 LF				
100 - PREP FOR PAINTING, 1'	320.00 each	0.60	1.00	INT. EXT. CUT LINE PAINTER
14 WD. TRIM PTD., , 334 LF				
100 - Apply Primer, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	400.00 LF	0.83	1.00	INTERIOR PAINTER

Production Report

PACSUN STORE

Bid No. 134

09900 Painting

FLOOR PLAN

Condition Labor Code	Pcs./Days	Crew Days	Crew	Installer
100 - Apply Finish Paint, PROGREEN 200 LATEX SEMI GLOSS	450.00 LF	0.74	1.00	INTERIOR TRIM PAINTER
100 - Apply Finish Paint, PROGREEN 200 LATEX SEMI GLOSS	450.00 LF	0.74	1.00	INTERIOR TRIM PAINTER
17 WD. DOOR PTD. & WD. FRAME PTD., 7' 0", 5 EA				
100 - Apply Primer, PREPRITE PROBLOCK INT/EXT. LATEX PRIMER SEALER	18.00 EA	0.28	1.00	MISCELLANEOUS TRIM PAINTER
100 - Apply Finish Paint, PM 200 0 VOC SEMIGLOSS	24.00 EA	0.21	1.00	MISCELLANEOUS TRIM PAINTER
100 - Apply Finish Paint, PM 200 0 VOC SEMIGLOSS	29.00 EA	0.17	1.00	MISCELLANEOUS TRIM PAINTER
100 - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	18.00 EA	0.28	1.00	MISCELLANEOUS TRIM PAINTER
100 - Apply Finish Paint, PM 200 0 VOC SEMIGLOSS	24.00 EA	0.21	1.00	MISCELLANEOUS TRIM PAINTER
100 - Apply Finish Paint, PM 200 0 VOC SEMIGLOSS	29.00 EA	0.17	1.00	MISCELLANEOUS TRIM PAINTER
19 12' DW WALLS LES, 12' 0", 2049 SF				
100 - Apply Primer, PROGREEN 200 LOW VOC PRIMER (1' x 1')	1,886.00 each	1.09	1.00	INTERIOR WALLS PAINTER
100 - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	2,401.00 SF	0.85	1.00	INTERIOR WALLS PAINTER
100 - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	2,813.00 SF	0.73	1.00	INTERIOR WALLS PAINTER
20 4'6" DW WALLS EPOXY, 4' 6", 129 SF				
100 - Apply Primer, PROGREEN 200 LOW VOC PRIMER (1' x 1')	1,886.00 each	0.07	1.00	INTERIOR WALLS PAINTER
100 - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	2,401.00 SF	0.05	1.00	INTERIOR WALLS PAINTER
100 - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	2,813.00 SF	0.05	1.00	INTERIOR WALLS PAINTER
21 19' DW PRIME ONLY, 19' 0", 2758 SF				
100 - Apply Primer, PROGREEN 200 LOW VOC PRIMER (1' x 1')	1,886.00 each	1.46	1.00	INTERIOR WALLS PAINTER
100 - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	2,401.00 SF	1.15	1.00	INTERIOR WALLS PAINTER
100 - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	2,813.00 SF	0.98	1.00	INTERIOR WALLS PAINTER
22 WD. SGL. FRAME PTD., 7' 0", 1 EA				
100 - Apply Primer, PREPRITE PROBLOCK INT/EXT. LATEX PRIMER SEALER	11.00 EA	0.09	1.00	MISCELLANEOUS TRIM PAINTER
100 - Apply Finish Paint, PM 200 0 VOC SEMIGLOSS	14.00 EA	0.07	1.00	MISCELLANEOUS TRIM PAINTER
100 - Apply Finish Paint, PM 200 0 VOC SEMIGLOSS	16.00 EA	0.06	1.00	MISCELLANEOUS TRIM PAINTER

RCP

Condition Labor Code	Pcs./Days	Crew Days	Crew	Installer
5 DW CLG. PTD. FLAT, , 242 SF				
100 - Apply Primer, PROGREEN 200 LOW VOC PRIMER	1,530.00 SF	0.16	1.00	INTERIOR CEILING PAINTER

Production Report

PACSUN STORE

Bid No. 134

09900 Painting

RCP

Condition Labor Code	Pcs./Days	Crew Days	Crew	Installer
100 - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	1,862.00 SF	0.13	1.00	INTERIOR CEILING PAINTER
100 - Apply Primer, PROGREEN 200 LOW VOC FLAT	2,071.00 SF	0.12	1.00	INTERIOR CEILING PAINTER
12 EXP. CONST. CLG. W / WATERBORNE ACRYLIC DRYFALL, , 3173 SF				
100 - Apply Finish Paint, WATERBORNE ACRYLIC EGGSHELL (1' x 1')	2,360.00 each	2.02	1.00	EXPOSED CONSTR. CEILING PAINTER
18 DW CLG. PTD. EPOXY, , 50 SF				
100 - Apply Primer, PROGREEN 200 LOW VOC PRIMER	1,530.00 SF	0.03	1.00	INTERIOR CEILING PAINTER
100 - Apply Finish Paint, PROGREEN 200 LOW VOC FLAT	1,862.00 SF	0.03	1.00	INTERIOR CEILING PAINTER
100 - Apply Primer, PROGREEN 200 LOW VOC FLAT	2,071.00 SF	0.02	1.00	INTERIOR CEILING PAINTER

INTERIOR ELEVATIONS

Condition Labor Code	Pcs./Days	Crew Days	Crew	Installer
1 AREA DW WALLS LES, , 314 SF				
100 - Apply Primer, PROGREEN 200 LOW VOC PRIMER (1' x 1')	1,886.00 each	0.17	1.00	INTERIOR WALLS PAINTER
100 - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	2,401.00 SF	0.13	1.00	INTERIOR WALLS PAINTER
100 - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	2,813.00 SF	0.11	1.00	INTERIOR WALLS PAINTER

BARCADE PLAN ELEVATION

Condition Labor Code	Pcs./Days	Crew Days	Crew	Installer
1 AREA DW WALLS LES, , 512 SF				
100 - Apply Primer, PROGREEN 200 LOW VOC PRIMER (1' x 1')	1,886.00 each	0.27	1.00	INTERIOR WALLS PAINTER
100 - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	2,401.00 SF	0.21	1.00	INTERIOR WALLS PAINTER
100 - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	2,813.00 SF	0.18	1.00	INTERIOR WALLS PAINTER
16 WD. DOOR PTD., 7' 0", 2 EA				
100 - Apply Primer, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	18.00 EA	0.11	1.00	MISCELLANEOUS TRIM PAINTER
100 - Apply Finish Paint, PM 200 0 VOC SEMIGLOSS	24.00 EA	0.08	1.00	MISCELLANEOUS TRIM PAINTER
100 - Apply Finish Paint, PM 200 0 VOC SEMIGLOSS	29.00 EA	0.07	1.00	MISCELLANEOUS TRIM PAINTER