

Purchasing Report

PACSUN STORE

Bid No. 134

Selected Sections: 02000 Misc. Bid Items, 09900 Painting

Selected Typical Areas:

Selected Areas: (unassigned), FLOOR PLAN, RCP, INTERIOR ELEVATIONS, DOORS/FRAMES, BARCADE PLAN ELEVATION

Estimator:

Job Class:

Wage Type: **Open**

Job Status: **PENDING**

Bid Date/Time: **1/8/2015 3:16:43 PM**

Plans Date: **12/3/2014**

PAYROLL @ \$40.00

02000 Misc. Bid Items (unassigned)

Equipment	Quantity	Ordered	Quoted	Paid	Total
LIFTS					
15 FT. ELECTRIC SCISSOR LIFT WEEK	1.00 WEEK	_____	325.00	_____	325.00

09900 Painting FLOOR PLAN

Materials	Quantity	Pieces	Ordered	Quoted	Paid	Total
FINISH						
WOOD BASE FINISH PAINTED LF, PROGREEN 200 LATEX SEMIGLOSS	601.27 LF	1.50 GALLONS	_____	18.59 / container	_____	27.94
FINISH PAINT WOOD DOOR, PM 200 0 VOC SEMIGLOSS	10.00 EA	1.25 GALLONS	_____	18.59 / container	_____	23.24
FINISH PAINT WOOD DOOR FRAME, PM 200 0 VOC SEMIGLOSS	12.00 EA	1.50 GALLONS	_____	18.95 / container	_____	28.43
LATEX						
PROGREEN 200, PROGREEN 200 LATEX SEMI GLOSS	667.17 LF	1.67 GALLONS	_____	24.00 / container	_____	40.03
PRIMERS						
WOOD BASE PRIMED, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	300.64 LF	0.75 GALLONS	_____	26.99 / container	_____	20.29
PRIME WOOD DOOR FRAME, PREPRITE PROBLOCK INT/EXT. LATEX PRIMER SEALER	6.00 EA	0.75 GALLONS	_____	26.99 / container	_____	20.24
PRIME WOOD DOOR, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	5.00 EA	0.63 GALLONS	_____	26.99 / container	_____	16.87
WOOD TRIM PRIMED, PREPRITE PROBLOCK INT/EXT LATEX PRIMER/SEALER	333.58 LF	0.83 GALLONS	_____	18.00 / container	_____	15.01

RCP

Materials	Quantity	Pieces	Ordered	Quoted	Paid	Total
DRYFALL						
DRYFALL FOR EXPOSED CONSTRUCTION CEILING, WATERBORNE ACRYLIC EGGSHELL (1' x 1')	4,758.85 SF	73.21 GALLON	_____	13.99 / container	_____	1,024.25

BARCADE PLAN ELEVATION

Materials	Quantity	Pieces	Ordered	Quoted	Paid	Total
FINISH						

Purchasing Report

PACSUN STORE

Bid No. 134

09900 Painting

BARACADE PLAN ELEVATION

Materials	Quantity	Pieces	Ordered	Quoted	Paid	Total
FINISH						
FINISH PAINT WOOD DOOR, PM 200 0 VOC SEMIGLOSS	4.00 EA	0.50 GALLONS	_____	18.59 / container _____		9.30
PRIMERS						
PRIME WOOD DOOR, PREPRITE PROBLOCK INT./EXT. LATEX PRIMER/SEALER	2.00 EA	0.25 GALLONS	_____	26.99 / container _____		6.75

Purchasing Report

PACSUN STORE

Bid No. 134

Purchase Order for SHERWIN WILLIAMS

09900 Painting

FLOOR PLAN

Materials	Quantity	Pieces	Ordered	Quoted	Paid	Total
-----------	----------	--------	---------	--------	------	-------

LATEX

HOLLOW METAL DOOR FRAME, DTM ACRYLIC SEMIGLOSS (DRS./ FR.)	6.00 EA	0.75 GALLONS	_____	30.88 / container _____		23.16
--	---------	--------------	-------	-------------------------	--	-------

HOLLOW METAL DOOR, DTM ACRYLIC SEMIGLOSS (DRS./ FR.)	6.00 EA	1.00 GALLONS	_____	32.00 / container _____		32.00
--	---------	--------------	-------	-------------------------	--	-------

METAL PAINT

INDUSTRIAL ENAMEL, PROINDUSTRIAL INDUSTRIAL ENAMEL (STEELCOLUMN)	6.00 EA	1.50 GALLON	_____	34.00 / container _____		51.00
--	---------	-------------	-------	-------------------------	--	-------

PRIMERS

P-1 PROMAR 200 LATEX PRIMER, PROGREEN 200 LOW VOC PRIMER (1' x 1') (P-1 PRIMER LATEX)	8,751.04 SF	21.88 GALLONS	_____	23.11 / container _____		505.59
---	-------------	---------------	-------	-------------------------	--	--------

P-1 PROGREEN 200, PROGREEN 200 LOW VOC LATEX EGGSHELL (P-1 WALLS W/STYLE)	17,502.08 SF	43.76 GALLONS	_____	16.85 / container _____		737.28
---	--------------	---------------	-------	-------------------------	--	--------

RCP

Materials	Quantity	Pieces	Ordered	Quoted	Paid	Total
-----------	----------	--------	---------	--------	------	-------

FINISH

P-1 PROGREEN 200 (sizes 2) (P-1 LATEXFLAT CLG)	877.68 SF	2.19 GALLONS	_____	15.75 / container _____		34.56
--	-----------	--------------	-------	-------------------------	--	-------

INTERIOR ELEVATIONS

Materials	Quantity	Pieces	Ordered	Quoted	Paid	Total
-----------	----------	--------	---------	--------	------	-------

PRIMERS

P-1 PROMAR 200 LATEX PRIMER, PROGREEN 200 LOW VOC PRIMER (1' x 1') (P-1 PRIMER LATEX)	313.51 SF	0.78 GALLONS	_____	23.11 / container _____		18.11
---	-----------	--------------	-------	-------------------------	--	-------

P-1 PROGREEN 200, PROGREEN 200 LOW VOC LATEX EGGSHELL (P-1 WALLS W/STYLE)	627.01 SF	1.57 GALLONS	_____	16.85 / container _____		26.41
---	-----------	--------------	-------	-------------------------	--	-------

BARACADE PLAN ELEVATION

Materials	Quantity	Pieces	Ordered	Quoted	Paid	Total
-----------	----------	--------	---------	--------	------	-------

PRIMERS

P-1 PROMAR 200 LATEX PRIMER, PROGREEN 200 LOW VOC PRIMER (1' x 1') (P-1 PRIMER LATEX)	511.72 SF	1.28 GALLONS	_____	23.11 / container _____		29.56
---	-----------	--------------	-------	-------------------------	--	-------

P-1 PROGREEN 200, PROGREEN 200 LOW VOC LATEX EGGSHELL (P-1 WALLS W/STYLE)	1,023.44 SF	2.56 GALLONS	_____	16.85 / container _____		43.11
---	-------------	--------------	-------	-------------------------	--	-------